

# REMORA HEAT PUMPS

## WI-FI EXTENSION CABLE REMOVAL



Remora On/Off and Inverter heat pumps come with a Wi-Fi module pre-installed on a 10m extension cable, the extension cable can be removed if not required and the module installed inside the unit.

### IMPORTANT

- Power to the unit **MUST** be completely isolated before removing cable cover or lid
- Ensure you have first connected the Wi-Fi and have sufficient signal before proceeding

**Step one:** isolate power, remove both the cable cover from side of unit and the lid from the top of the unit, put the covers and screws carefully to one side.

**Step two:** trace the white Wi-Fi extension cables back to the two black connection clips inside the unit (located near the wire bundle as seen in picture one).

**Step three:** unclip one of the extension cables from the black clip inside the unit- do not unclip them both at the same time.


**Step four:** gently remove the loose extension cable through the side of the heat pump, unclip the extension cable from the Wi-Fi module.

**Step five:** clip the short cable from the Wi-Fi module into the now empty clip inside the unit (picture one).

**Step six:** repeat for the second extension cable.

**Step seven:** carefully place the Wi-Fi module inside the unit as per picture two, the module is magnetic and will stick to the metal casing inside the unit - be careful to avoid the pressure gauge pipe (circled).

**Step eight:** secure the lid and cable cover back on the unit, power up the heat pump and test the Wi-Fi connection to the unit.



2